BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule-B"

Name of Work :- Operation and Maintenance of Street Lighting System in Ward No.07 Package Y-7 of Yelahanka Zone.

Sl. No	Qty	Description Of Work	Unit	Approved Rates	
				In figures	In words
1	444	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. i) Poles with 36/40 W fluorescent tube light street lighting system.	Each	95.00	Rupees Ninety Five Only
2	75	Poles with 125 W MV light Park lighting system.	Each	325.00	Rupees Three Hundred Twenty Five Only
3	3197	Poles with 250W HPSV light street lighting system.	Each	552.00	Rupees Five Hundred Fifty Two Only
4	58	Poles with 400 watts HPSV light street lighting system.	Each	825.00	Rupees Eight Hundred Twenty Five Only
5	40	Poles with 24 W LED light street lighting system.	Each	880.00	Rupees Eight Hundred Eighty Only
6	340	Poles with 65 W LED light street lighting system.	Each	1140.00	Rupees One Thousand One Hundred Forty Only
7	65	Poles with 90 W LED light street lighting system.	Each	1300.00	Rupees One Thousand Three Hundred Only
8	125	Poles with 110/120 W LED light street lighting system.	Each	1475.00	Rupees One Thousand Four Hundred Seventy Five Only
9	25	Operation and maintenance of Manual and Automatic Timer Switching circuits including replacement of electrical gadgets, such as MCB's Contactors, Timer, Cut-outs, wiring connector and M.S. Box with proper insulation etc., complete.	Each	1200.00	Rupees One Thousand Two Hundred Only
10	75	B. Work to be carried out as per requirement & actuals and as per the direction of the in charge engineer, Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/looting of the pole.a)5 mtr pole	Each	325.00	Rupees Three Hundred Twenty Five Only

Executive Engineer
Electrical Division
Yelahanka Zone BBMP
Kempegowda Layout, Bangalore-63

11	80	c) 8 Mtr and above street light pole	Each	525.00	Rupees Five Hundred Twenty Five Only
12	20	Moulded Case Circuit Breaker (MCCB) Three Pole 100Amps 25kA	Each	2708.00	Rupees Two Thousand Seven Hundred Eight Only
13	20	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop-Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.200mmx200mmx98mm	Each	1850.00	Rupees One Thousand Eight Hundred Fifty Only

I am prepared to take up the above work at rates quoted in the Schedule 'B'

Contractor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone